

N288. Temporary Shielding for RHR Piping

A temporary shielding package for the large bore RHR (residual heat removal) piping on top of the unit 3 Taurus of Browns Ferry Nuclear Plant has just been installed. The insulator craftsmen did an outstanding job installing over 1,000 lead wool blankets directly on the RHR piping. This shielding was installed to support recovery modifications starting with tours platform steel.

In addition, this shielding is expected to remain in place during recovery and will provide significant man-rem savings for other recovery tasks.

Taken from, "Temporary Shielding," Browns Ferry Nuclear Plant Radcon News, p.2, July 1993. For further information call Mike Scarboro (Editor) at 205/729-3400.